

# Appendix C: Geotechnical Report



CONSULTANTS  
· ENVIRONMENTAL  
· GEOTECHNICAL  
· MATERIALS  
· FORENSICS

August 17, 2020

Ms. Paige Attarian  
City of Skyline  
164 S Skyline Drive  
Mankato, MN 56001  
[paigecpa@charter.net](mailto:paigecpa@charter.net)

RE: Geotechnical Exploration and Review  
Elevated Water Storage Tank  
Skyline, Minnesota  
AET #08-20737

Dear Ms. Attarian:

This letter report presents the results of the standard penetration test borings conducted on August 4, 2020 in Skyline, Minnesota. The work was performed in accordance with our proposal dated June 29, 2020. The scope of work related to this request includes the following:

- Two (2) standard penetration test borings to depths of 50 feet.
- Soil laboratory testing (water content, density, unconfined compressive strength).
- Preparation of this letter report, discussing the in-place soil and ground water conditions encountered and general comments on foundation support of proposed elevated water storage tank.

We have included one electronic copy of our report. Additional copies are being sent on your behalf as noted below.

### **1.0 Project Information**

We understand that you are planning to construct a 50,000 gallon pedosphere-style or hydrocone-style elevated water tower structure. We do not have any specific structural loading information; we assume moderate to heavy loads for a structure of this type. We assume that the finished grade for the structure will be within one to two feet of the current surface grade.

As discussed in our proposal dated June 29, 2020; we understand after the final elevated storage tank location is selected an additional soil boring will be performed and a final Geotechnical Engineering Report will be completed for the structure.

## **2.0 Site Exploration**

Logs of the test borings are attached. The logs contain information concerning soil layering, soil classification, geologic description, and moisture condition. Relatively density or consistency is also noted, which is based on the standard penetration resistance (N-value).

We refer you to the standard sheet entitled “Exploration/Classification Methods” for details on the drilling and the sampling methods, and the water level measurement methods. Data sheets concerning the Unified Soils Classification System, the descriptive terminology, and the symbols used on the boring logs are also attached.

The test boring locations are shown on Figure 2. The surface elevations shown on the logs were provided by ISG personnel.

## **3.0 Conditions Encountered**

### **3.1 Soils**

The site geology consists of fill with clay till present at depth.

The surficial fill layer was about 1’ to 2’ deep at the boring locations. The fill consisted of black and gray organic lean clay to brown and dark brown sandy lean clay.

Sandy lean clay and clayey sand, glacial till was encountered from below the surficial fill to the boring termination depth. The till varied in color from brown and gray mottled to brown in the upper soil profile to gray at depth. Additionally, the till contained some gravel and numerous lenses and layers of sand. The consistency of the till varied from firm to hard.

### **3.2 Groundwater**

Subsurface water was noted at boring location B-1 at 46.6 feet below existing site grade at the time our field work was performed. Groundwater levels fluctuate due to varying seasonal and annual rainfall and snow melt amounts, as well as other factors.

Based upon our previous experience with clay till soils in the general project area, it is our opinion that the subsurface water levels at the site could be quite near the ground surface during periods of significant precipitation, particularly during the spring of the year. It should also be recognized that groundwater levels can fluctuate due to natural seasonal variations in rainfall and snowmelt amounts.

#### **4.0 Geotechnical Review**

We understand that you are planning to construct a 50,000 gallon pedosphere-style or hydrocone-style with a ring foundation, elevated water tower structure. As discussed in our proposal dated June 29, 2020; two proposed borings were advanced at the staked locations, one at each of the possible locations. Boring B-1 was advanced just west of the existing water tower and B-2 was advanced approximately 100 feet to the east of the existing water tower.

Based on the soil boring information obtained, the proposed elevated water storage tower can be suitably supported at either location. We anticipate typical elevated water storage tower ring wall foundations will be 6 to 8 feet below finished grade. The naturally occurring soils encountered within both soil borings at these proposed foundation support depths should be suitable for support for the proposed elevated water storage tank. We anticipate soil contact pressures in the range of 2,000 to 3,000 psf can be obtained. We understand after the final site is selected a second soil boring will be advanced within the foundation area of the proposed elevated water storage tank. Based on the results of both soil borings, a final Geotechnical Engineering Report can be prepared specific earthwork recommendations, foundation soil contact pressures, and anticipated settlements.

The proposed construction is located on fairly level topography adjacent to fairly steep hillsides/ravines sloping downward to the south and east, away from the project area. The existing water tower and other structures in the area are also located adjacent to the hillside and we are not aware of the any significant problems that have occurred. The risk of detrimental movement is, however, present along such hillsides. Based upon the boring information and our knowledge of the site history, it does not appear that a deep seated, slope failure is a significant risk at this site. Deeper penetration borings and a slope stability analysis would be required to better define the magnitude of risk.

Also, of concern is the possibility of shallow movement due to saturation of the upper soils. The magnitude of risk for this type of movement is very difficult to quantify although the risk is certainly present at this site. Prudent measures that should be taken to reduce the risk of a shallow, surface slide include maintaining surface vegetation and trees along the hillside and diverting surface runoff away from the hillside and ravine areas.

#### **5.0 Limitations**

Within the limitations of scope, budget, and schedule, our services have been conducted according to generally accepted geotechnical engineering practices at this time and location. Other than this, no warranty, either expressed or implied, is intended.


Important information regarding risk management and proper use of this report is given in the attached sheet entitled "Geotechnical Report Limitations and Guidelines for Use".

City of Skyline  
Page 4 of 6  
August 17, 2020  
AET #08-20737

### 6.0 Remarks

We appreciate being giving the opportunity to work with you on your project. If you have any questions regarding the work reported herein, please do not hesitate to contact us at (507) 387-2222 or [gguyer@amengtest.com](mailto:gguyer@amengtest.com).

Sincerely,  
**American Engineering Testing, Inc.**



Gregory A. Guyer, PE  
Manager – Mankato  
MN Reg. No. 44618  
[gguyer@amengtest.com](mailto:gguyer@amengtest.com)

Report Reviewed By:  
**American Engineering Testing, Inc.**




Steven J. Ruesink, PE  
Regional Manager  
MN Reg. No. 19431  
[sruessink@amengtest.com](mailto:sruessink@amengtest.com)

GAG/SJR/lmh

cc: ISG - Bryan Petzel

### Attachments

- Figure 1 – Site Location
- Figure 2 – Boring Locations
- Subsurface Boring Logs
- Exploration/Classification Methods
- Boring Log Notes
- Unified Soil Classification System
- Geotechnical Report Limitations and Guidelines For Use



Project: Elevated Water Storage Tank  
Skyline, MN

AET Job No. 08-20737

Subject: Site Location

Date: Aug. 17, 2020

Scale: NTS

Drawn By: GG

Checked By: SR

Figure: 1



Project	Elevated Water Storage Tank Skyline, MN	Subject:	Boring Locations	AET Job No:	08-20737	Date:	Aug. 17, 2020
Scale:	NTS	Drawn By:	GG	Checked By:	SR	Figure 2	



# SUBSURFACE BORING LOG

AET No: 08-20737

Log of Boring No. B-1 (p. 1 of 1)

Project: Elevated Water Storage Tank; Syline, Minnesota

DEPTH IN FEET	Surface Elevation <u>984.1'</u> MATERIAL DESCRIPTION	GEOLOGY	N	MC	SAMPLE TYPE	REC IN.	FIELD & LABORATORY TESTS							
							WC	DEN	qp	qu				
1	FILL, sandy lean clay w/visible organics, dark brown	FILL		M	FA									
2														
3	FILL, sandy lean clay, brown	TILL	8	M	SS	15	22							
4														
5	SANDY LEAN CLAY, brown, firm (CL)													
6	SANDY LEAN CLAY, brown and gray mottled, stiff (CL)		9	M	SS	18	23							
7														
8	SANDY LEAN CLAY, a little gravel, brown w/red iron staining, stiff (CL)		12	M	SS	20	22							
9														
10			12	M	SS	20	22							
11														
12			11	M	SS	20	23							
13														
14														
15														
16														
17														
18				M	TW	18	24	93				3800		
19														
20	SANDY LEAN CLAY, brown, hard, sand seam at 20' (CL)		31	W	SS	12								
21														
22														
23														
24														
25	SANDY LEAN CLAY, gray, very stiff (CL)		28	M	SS	18	18							
26														
27														
28														
29														
30	CLAYEY SAND, a little gravel, gray, stiff to hard (SC)		36	W	SS	3								
31														
32														
33														
34														
35														
36			13	M	SS	20	22							
37														
38														
39														
40														
41			13	M	SS	24								
42														
43														
44														
45														
46			16	▼	SS	24								
47														
48														
49														
50														
51	<b>END OF BORING</b>		24	M	SS	24								

AET\_CORP 08-20737.ELEVATED WATER STORAGE TANK - SKYLINE.GPJ AET+CPT+WELL.GDT 8/17/20

DEPTH:	DRILLING METHOD	WATER LEVEL MEASUREMENTS							NOTE: REFER TO THE ATTACHED SHEETS FOR AN EXPLANATION OF TERMINOLOGY ON THIS LOG
<b>0-49½'</b>	<b>3.25" HSA</b>	DATE	TIME	SAMPLED DEPTH	CASING DEPTH	CAVE-IN DEPTH	DRILLING FLUID LEVEL	WATER LEVEL	
		<b>8/4/20</b>	<b>10:30</b>	<b>51'</b>	<b>49.5'</b>	<b>49.5'</b>	<b>None</b>	<b>50.2'</b>	
		<b>8/4/20</b>	<b>10:45</b>	<b>51'</b>	<b>49.5'</b>	<b>49.5'</b>	<b>None</b>	<b>46.6'</b>	
BORING COMPLETED: <b>8/4/20</b>									
DR: <b>TW</b> LG: <b>CH</b> Rig: <b>84R</b>									





# SUBSURFACE BORING LOG

AET No: 08-20737

Log of Boring No. B-2 (p. 1 of 1)

Project: Elevated Water Storage Tank; Syline, Minnesota

DEPTH IN FEET	Surface Elevation <u>982.9'</u> MATERIAL DESCRIPTION	GEOLOGY	N	MC	SAMPLE TYPE	REC IN.	FIELD & LABORATORY TESTS				
							WC	DEN	qp	qu	
1	FILL, organic lean clay, black and gray	FILL TILL		M	FA						
2	SANDY LEAN CLAY, brown, firm (CL)										
3	SANDY LEAN CLAY, a little gravel, brown, stiff (CL)		8	M	SS	15	24				
4											
5	SANDY LEAN CLAY, a little gravel, brown, stiff (CL)		10	M	SS	20	21				
6											
7	SANDY LEAN CLAY, brown and gray mottled, stiff (CL)		10	M	SS	20	23				
8											
9											
10			12	M	SS	20					
11											
12											
13			11	M	SS	20	20				
14											
15											
16											
17											
18				M	TW	23	25	92		4260	
19											
20	SANDY LEAN CLAY, dark brown, very stiff (CL)		16	M	SS	20	22				
21											
22											
23											
24											
25											
26			20	M	SS	20	18				
27											
28											
29											
30	SANDY LEAN CLAY, gray w/red rust staining, very stiff (CL)		25	M	SS	24	23				
31											
32											
33											
34											
35	SANDY LEAN CLAY, a little gravel, gray, stiff to very stiff (CL)		15	M	SS	20	20				
36											
37											
38											
39											
40											
41											
42											
43											
44											
45											
46											
47											
48											
49											
50											
51	<b>END OF BORING</b>		24	M	SS	24					

AET\_CORP 08-20737.ELEVATED WATER STORAGE TANK - SKYLINE.GPJ AET+CPT+WELL.GDT 8/17/20

DEPTH:	DRILLING METHOD	WATER LEVEL MEASUREMENTS							NOTE: REFER TO THE ATTACHED SHEETS FOR AN EXPLANATION OF TERMINOLOGY ON THIS LOG
<b>0-49½'</b>	<b>3.25" HSA</b>	DATE	TIME	SAMPLED DEPTH	CASING DEPTH	CAVE-IN DEPTH	DRILLING FLUID LEVEL	WATER LEVEL	
		<b>8/4/20</b>	<b>1:45</b>	<b>51'</b>	<b>49.5'</b>	<b>49.5'</b>	<b>None</b>	<b>None</b>	
		<b>8/4/20</b>	<b>2:00</b>	<b>51'</b>	<b>--</b>	<b>--</b>	<b>None</b>	<b>None</b>	
BORING COMPLETED: <b>8/4/20</b>									
DR: <b>TW</b> LG: <b>CH</b> Rig: <b>84R</b>									

## **EXPLORATION/CLASSIFICATION METHODS**

---

### **SAMPLING METHODS**

---

#### **Split-Spoon Samples (SS)**

Standard penetration (split-spoon) samples were collected in general accordance with ASTM:D1586. This method consists of driving a 2" O.D. split barrel sampler into the in-situ soil with a 140-pound hammer dropped from a height of 30". The sampler is driven a total of 18" into the soil. After an initial set of 6", the number of hammer blows to drive the sampler the final 12" is known as the standard penetration resistance or N-value.

#### **Disturbed Samples (DS)/Spin-up Samples (SU)**

Sample types described as "DS" or "SU" on the boring logs are disturbed samples, which are taken from the flights of the auger. Because the auger disturbs the samples, possible soil layering and contact depths should be considered approximate.

#### **Sampling Limitations**

Unless actually observed in a sample, contacts between soil layers are estimated based on the spacing of samples and the action of drilling tools. Cobbles, boulders, and other large objects generally cannot be recovered from test borings, and they may be present in the ground even if they are not noted on the boring logs.

### **CLASSIFICATION METHODS**

---

Soil classifications shown on the boring logs are based on the Unified Soil Classification (USC) system. The USC system is described in ASTM:D2487 and D2488. Where laboratory classification tests (sieve analysis or Atterberg Limits) have been performed, accurate classifications per ASTM: D2487 are possible. Otherwise, soil classifications shown on the boring logs are visual-manual judgments. Charts are attached which provide information on the USC system, the descriptive terminology, and the symbols used on the boring logs.

The boring logs include descriptions of apparent geology. The geologic depositional origin of each soil layer is interpreted primarily by observation of the soil samples, which can be limited. Observations of the surrounding topography, vegetation, and development can sometimes aid this judgment.

### **WATER LEVEL MEASUREMENTS**

---

The ground water level measurements are shown at the bottom of the boring logs. The following information appears under "Water Level Measurements" on the logs:

- Date and Time of measurement
- Sampled Depth: lowest depth of soil sampling at the time of measurement
- Casing Depth: depth to bottom of casing or hollow-stem auger at time of measurement
- Cave-in Depth: depth at which measuring tape stops in the borehole
- Water Level: depth in the borehole where free water is encountered
- Drilling Fluid Level: same as Water Level, except that the liquid in the borehole is drilling fluid

The true location of the water table at the boring locations may be different than the water levels measured in the boreholes. This is possible because there are several factors that can affect the water level measurements in the borehole. Some of these factors include: permeability of each soil layer in profile, presence of perched water, amount of time between water level readings, presence of drilling fluid, weather conditions, and use of borehole casing.

### **SAMPLE STORAGE**

---

Unless notified to do otherwise, we routinely retain representative samples of the soils recovered from the borings for a period of 30 days.

## BORING LOG NOTES

### DRILLING AND SAMPLING SYMBOLS

Symbol	Definition
AR:	Sample of material obtained from cuttings blown out the top of the borehole during air rotary procedure.
B, H, N:	Size of flush-joint casing
CAS:	Pipe casing, number indicates nominal diameter in inches
COT:	Clean-out tube
DC:	Drive casing; number indicates diameter in inches
DM:	Drilling mud or bentonite slurry
DR:	Driller (initials)
DS:	Disturbed sample from auger flights
DP:	Direct push drilling; a 2.125 inch OD outer casing with an inner 1½ inch ID plastic tube is driven continuously into the ground.
FA:	Flight auger; number indicates outside diameter in inches
HA:	Hand auger; number indicates outside diameter
HSA:	Hollow stem auger; number indicates inside diameter in inches
LG:	Field logger (initials)
MC:	Column used to describe moisture condition of samples and for the ground water level symbols
N (BPF):	Standard penetration resistance (N-value) in blows per foot (see notes)
NQ:	NQ wireline core barrel
PQ:	PQ wireline core barrel
RDA:	Rotary drilling with compressed air and roller or drag bit.
RDF:	Rotary drilling with drilling fluid and roller or drag bit
REC:	In split-spoon (see notes), direct push and thin-walled tube sampling, the recovered length (in inches) of sample. In rock coring, the length of core recovered (expressed as percent of the total core run). Zero indicates no sample recovered.
SS:	Standard split-spoon sampler (steel; 1.5" is inside diameter; 2" outside diameter); unless indicated otherwise
SU	Spin-up sample from hollow stem auger
TW:	Thin-walled tube; number indicates inside diameter in inches
WASH:	Sample of material obtained by screening returning rotary drilling fluid or by which has collected inside the borehole after "falling" through drilling fluid
WH:	Sampler advanced by static weight of drill rod and hammer
WR:	Sampler advanced by static weight of drill rod
94mm:	94 millimeter wireline core barrel
▼:	Water level directly measured in boring
▽:	Estimated water level based solely on sample appearance

### TEST SYMBOLS

Symbol	Definition
CONS:	One-dimensional consolidation test
DEN:	Dry density, pcf
DST:	Direct shear test
E:	Pressuremeter Modulus, tsf
HYD:	Hydrometer analysis
LL:	Liquid Limit, %
LP:	Pressuremeter Limit Pressure, tsf
OC:	Organic Content, %
PERM:	Coefficient of permeability (K) test; F - Field; L - Laboratory
PL:	Plastic Limit, %
q <sub>p</sub> :	Pocket Penetrometer strength, tsf ( <u>approximate</u> )
q <sub>c</sub> :	Static cone bearing pressure, tsf
q <sub>u</sub> :	Unconfined compressive strength, psf
R:	Electrical Resistivity, ohm-cms
RQD:	Rock Quality Designation of Rock Core, in percent (aggregate length of core pieces 4" or more in length as a percent of total core run)
SA:	Sieve analysis
TRX:	Triaxial compression test
VSR:	Vane shear strength, remolded (field), psf
VSU:	Vane shear strength, undisturbed (field), psf
WC:	Water content, as percent of dry weight
%-200:	Percent of material finer than #200 sieve

### STANDARD PENETRATION TEST NOTES

#### (Calibrated Hammer Weight)

The standard penetration test consists of driving a split-spoon sampler with a drop hammer (calibrated weight varies to provide N<sub>60</sub> values) and counting the number of blows applied in each of three 6" increments of penetration. If the sampler is driven less than 18" (usually in highly resistant material), permitted in ASTM: D1586, the blows for each complete 6" increment and for each partial increment is on the boring log. For partial increments, the number of blows is shown to the nearest 0.1' below the slash.

The length of sample recovered, as shown on the "REC" column, may be greater than the distance indicated in the N column. The disparity is because the N-value is recorded below the initial 6" set (unless partial penetration defined in ASTM: D1586 is encountered) whereas the length of sample recovered is for the entire sampler drive (which may even extend more than 18").

**UNIFIED SOIL CLASSIFICATION SYSTEM**  
**ASTM Designations: D 2487, D2488**

**AMERICAN  
ENGINEERING  
TESTING, INC.**





Criteria for Assigning Group Symbols and Group Names Using Laboratory Tests <sup>A</sup>				Soil Classification		
				Group Symbol	Group Name <sup>B</sup>	
Coarse-Grained Soils More than 50% retained on No. 200 sieve	Gravels More than 50% coarse fraction retained on No. 4 sieve	Clean Gravels Less than 5% fines <sup>C</sup>	$Cu \geq 4$ and $1 \leq Cc \leq 3^E$	GW	Well graded gravel <sup>F</sup>	
			$Cu < 4$ and/or $1 > Cc > 3^E$	GP	Poorly graded gravel <sup>F</sup>	
	Sands 50% or more of coarse fraction passes No. 4 sieve	Clean Sands Less than 5% fines <sup>D</sup>	$Cu \geq 6$ and $1 \leq Cc \leq 3^E$	SW	Well-graded sand <sup>I</sup>	
			$Cu < 6$ and/or $1 > Cc > 3^E$	SP	Poorly-graded sand <sup>I</sup>	
	Sands with Fines more than 12% fines <sup>D</sup>	Fines classify as ML or MH		SM	Silty sand <sup>G,H,I</sup>	
		Fines classify as CL or CH		SC	Clayey sand <sup>G,H,I</sup>	
Fine-Grained Soils 50% or more passes the No. 200 sieve  (see Plasticity Chart below)	Sils and Clays Liquid limit less than 50	inorganic	$PI > 7$ and plots on or above "A" line <sup>J</sup>	CL	Lean clay <sup>K,L,M</sup>	
			$PI < 4$ or plots below "A" line <sup>J</sup>	ML	Silt <sup>K,L,M</sup>	
		organic	Liquid limit—oven dried $< 0.75$ Liquid limit – not dried		OL	Organic clay <sup>K,L,M,N</sup> Organic silt <sup>K,L,M,O</sup>
	Sils and Clays Liquid limit 50 or more	inorganic	PI plots on or above "A" line		CH	Fat clay <sup>K,L,M</sup>
			PI plots below "A" line		MH	Elastic silt <sup>K,L,M</sup>
		organic	Liquid limit—oven dried $< 0.75$ Liquid limit – not dried		OH	Organic clay <sup>K,L,M,P</sup> Organic silt <sup>K,L,M,Q</sup>
Highly organic soil	Primarily organic matter, dark in color, and organic in odor			PT	Peat <sup>R</sup>	

**Notes**  
<sup>A</sup>Based on the material passing the 3-in (75-mm) sieve.  
<sup>B</sup>If field sample contained cobbles or boulders, or both, add "with cobbles or boulders, or both" to group name.  
<sup>C</sup>Gravels with 5 to 12% fines require dual symbols:  
 GW-GM well-graded gravel with silt  
 GW-GC well-graded gravel with clay  
 GP-GM poorly graded gravel with silt  
 GP-GC poorly graded gravel with clay  
<sup>D</sup>Sands with 5 to 12% fines require dual symbols:  
 SW-SM well-graded sand with silt  
 SW-SC well-graded sand with clay  
 SP-SM poorly graded sand with silt  
 SP-SC poorly graded sand with clay

$${}^E C_u = D_{60} / D_{10}, \quad C_c = \frac{(D_{30})^2}{D_{10} \times D_{60}}$$

<sup>F</sup>If soil contains  $\geq 15\%$  sand, add "with sand" to group name.  
<sup>G</sup>If fines classify as CL-ML, use dual symbol GC-GM, or SC-SM.  
<sup>H</sup>If fines are organic, add "with organic fines" to group name.  
<sup>I</sup>If soil contains  $\geq 15\%$  gravel, add "with gravel" to group name.  
<sup>J</sup>If Atterberg limits plot is hatched area, soils is a CL-ML silty clay.  
<sup>K</sup>If soil contains 15 to 29% plus No. 200 add "with sand" or "with gravel", whichever is predominant.  
<sup>L</sup>If soil contains  $\geq 30\%$  plus No. 200, predominantly sand, add "sandy" to group name.  
<sup>M</sup>If soil contains  $\geq 30\%$  plus No. 200, predominantly gravel, add "gravelly" to group name.  
<sup>N</sup> $PI \geq 4$  and plots on or above "A" line.  
<sup>O</sup> $PI < 4$  or plots below "A" line.  
<sup>P</sup> $PI$  plots on or above "A" line.  
<sup>Q</sup> $PI$  plots below "A" line.  
<sup>R</sup>Fiber Content description shown below.



**ADDITIONAL TERMINOLOGY NOTES USED BY AET FOR SOIL IDENTIFICATION AND DESCRIPTION**

Grain Size		Gravel Percentages		Consistency of Plastic Soils		Relative Density of Non-Plastic Soils	
Term	Particle Size	Term	Percent	Term	N-Value, BPF	Term	N-Value, BPF
Boulders	Over 12"	A Little Gravel	3% - 14%	Very Soft	less than 2	Very Loose	0 - 4
Cobbles	3" to 12"	With Gravel	15% - 29%	Soft	2 - 4	Loose	5 - 10
Gravel	#4 sieve to 3"	Gravelly	30% - 50%	Firm	5 - 8	Medium Dense	11 - 30
Sand	#200 to #4 sieve			Stiff	9 - 15	Dense	31 - 50
Fines (silt & clay)	Pass #200 sieve			Very Stiff	16 - 30	Very Dense	Greater than 50
				Hard	Greater than 30		
Moisture/Frost Condition (MC Column)		Layering Notes		Peat Description		Organic Description (if no lab tests)	
D (Dry):	Absence of moisture, dusty, dry to touch.	Laminations:	Layers less than 1/2" thick of differing material or color.	Term	Fiber Content (Visual Estimate)	Soils are described as <i>organic</i> , if soil is not peat and is judged to have sufficient organic fines content to influence the Liquid Limit properties. <i>Slightly organic</i> used for borderline cases.	
M (Moist):	Damp, although free water not visible. Soil may still have a high water content (over "optimum").			Fibric Peat:	Greater than 67%	Root Inclusions	
W (Wet/Waterbearing):	Free water visible intended to describe non-plastic soils. Waterbearing usually relates to sands and sand with silt.	Lenses:	Pockets or layers greater than 1/2" thick of differing material or color.	Hemic Peat:	33 - 67%	With roots: Judged to have sufficient quantity of roots to influence the soil properties.	
F (Frozen):	Soil frozen			Sapric Peat:	Less than 33%	Trace roots: Small roots present, but not judged to be in sufficient quantity to significantly affect soil properties.	

# Geotechnical Report Limitations and Guidelines for Use

## AET Project No. 08-20737

---

### B.1 REFERENCE

This appendix provides information to help you manage your risks relating to subsurface problems which are caused by construction delays, cost overruns, claims, and disputes. This information was developed and provided by ASFE<sup>1</sup>, of which, we are a member firm.

### B.2 RISK MANAGEMENT INFORMATION

#### B.2.1 Geotechnical Services are Performed for Specific Purposes, Persons, and Projects

Geotechnical engineers structure their services to meet the specific needs of their clients. A geotechnical engineering study conducted for a civil engineer may not fulfill the needs of a construction contractor or even another civil engineer. Because each geotechnical engineering study is unique, each geotechnical engineering report is unique, prepared solely for the client. No one except you should rely on your geotechnical engineering report without first conferring with the geotechnical engineer who prepared it. And no one, not even you, should apply the report for any purpose or project except the one originally contemplated.

#### B.2.2 Read the Full Report

Serious problems have occurred because those relying on a geotechnical engineering report did not read it all. Do not rely on an executive summary. Do not read selected elements only.

#### B.2.3 A Geotechnical Engineering Report is Based on A Unique Set of Project-Specific Factors

Geotechnical engineers consider a number of unique, project-specific factors when establishing the scope of a study. Typically factors include: the client's goals, objectives, and risk management preferences; the general nature of the structure involved, its size, and configuration; the location of the structure on the site; and other planned or existing site improvements, such as access roads, parking lots, and underground utilities. Unless the geotechnical engineer who conducted the study specifically indicates otherwise, do not rely on a geotechnical engineering report that was:

- ♦ not prepared for you,
- ♦ not prepared for your project,
- ♦ not prepared for the specific site explored, or
- ♦ completed before important project changes were made.

Typical changes that can erode the reliability of an existing geotechnical engineering report include those that affect:

- ♦ the function of the proposed structure, as when it's changed from a parking garage to an office building, or from a light industrial plant to a refrigerated warehouse,
- ♦ elevation, configuration, location, orientation, or weight of the proposed structure,
- ♦ composition of the design team, or
- ♦ project ownership.

As a general rule, always inform your geotechnical engineer of project changes, even minor ones, and request an assessment of their impact. Geotechnical engineers cannot accept responsibility or liability for problems that occur because their reports do not consider developments of which they were not informed.

#### B.2.4 Subsurface Conditions Can Change

A geotechnical engineering report is based on conditions that existed at the time the study was performed. Do not rely on a geotechnical engineering report whose adequacy may have been affected by: the passage of time; by man-made events, such as construction on or adjacent to the site; or by natural events, such as floods, earthquakes, or groundwater fluctuations. Always contact the geotechnical engineer before applying the report to determine if it is still reliable. A minor amount of additional testing or analysis could prevent major problems.

---

1 ASFE, 8811 Colesville Road/Suite G106, Silver Spring, MD 20910  
Telephone: 301/565-2733: [www.asfe.org](http://www.asfe.org)

# **Geotechnical Report Limitations and Guidelines for Use**

## **AET Project No. 08-20737**

---

### **B.2.5 Most Geotechnical Findings Are Professional Opinions**

Site exploration identified subsurface conditions only at those points where subsurface tests are conducted or samples are taken. Geotechnical engineers review field and laboratory data and then apply their professional judgment to render an opinion about subsurface conditions throughout the site. Actual subsurface conditions may differ, sometimes significantly, from those indicated in your report. Retaining the geotechnical engineer who developed your report to provide construction observation is the most effective method of managing the risks associated with unanticipated conditions.

### **B.2.6 A Report's Recommendations Are Not Final**

Do not overrely on the construction recommendations included in your report. Those recommendations are not final, because geotechnical engineers develop them principally from judgment and opinion. Geotechnical engineers can finalize their recommendations only by observing actual subsurface conditions revealed during construction. The geotechnical engineer who developed your report cannot assume responsibility or liability for the report's recommendations if that engineer does not perform construction observation.

### **B.2.7 A Geotechnical Engineering Report Is Subject to Misinterpretation**

Other design team members' misinterpretation of geotechnical engineering reports has resulted in costly problems. Lower that risk by having your geotechnical engineer confer with appropriate members of the design team after submitting the report. Also retain your geotechnical engineer to review pertinent elements of the design team's plans and specifications. Contractors can also misinterpret a geotechnical engineering report. Reduce that risk by having your geotechnical engineer participate in prebid and preconstruction conferences, and by providing construction observation.

### **B.2.8 Do Not Redraw the Engineer's Logs**

Geotechnical engineers prepare final boring and testing logs based upon their interpretation of field logs and laboratory data. To prevent errors or omissions, the logs included in a geotechnical engineering report should never be redrawn for inclusion in architectural or other design drawings. Only photographic or electronic reproduction is acceptable, but recognizes that separating logs from the report can elevate risk.

### **B.2.9 Give Contractors a Complete Report and Guidance**

Some owners and design professionals mistakenly believe they can make contractors liable for unanticipated subsurface conditions by limiting what they provide for bid preparation. To help prevent costly problems, give contractors the complete geotechnical engineering report, but preface it with a clearly written letter of transmittal. In the letter, advise contractors that the report was not prepared for purposes of bid development and that the report's accuracy is limited; encourage them to confer with the geotechnical engineer who prepared the report (a modest fee may be required) and/or to conduct additional study to obtain the specific types of information they need or prefer. A prebid conference can also be valuable. Be sure contractors have sufficient time to perform additional study. Only then might you be in a position to give contractors the best information available to you, while requiring them to at least share some of the financial responsibilities stemming from unanticipated conditions.

### **B.2.10 Read Responsibility Provisions Closely**

Some clients, design professionals, and contractors do not recognize that geotechnical engineering is far less exact than other engineering disciplines. This lack of understanding has created unrealistic expectations that have led to disappointments, claims, and disputes. To help reduce the risk of such outcomes, geotechnical engineers commonly include a variety of explanatory provisions in their report. Sometimes labeled "limitations" many of these provisions indicate where geotechnical engineers' responsibilities begin and end, to help others recognize their own responsibilities and risks. Read these provisions closely. Ask questions. Your geotechnical engineer should respond fully and frankly.

### **B.2.11 Geoenvironmental Concerns Are Not Covered**

The equipment, techniques, and personnel used to perform a geoenvironmental study differ significantly from those used to perform a geotechnical study. For that reason, a geotechnical engineering report does not usually relate any geoenvironmental findings, conclusions, or recommendations; e.g., about the likelihood of encountering underground storage tanks or regulated contaminants. Unanticipated environmental problems have led to numerous project failures. If you have not yet obtained your own geoenvironmental information, ask your geotechnical consultant for risk management guidance. Do not rely on an environmental report prepared for someone else

# Appendix D: MDH Well Reports

147952

County Blue Earth  
 Quad Mankato  
 Quad ID 56A

MINNESOTA DEPARTMENT OF HEALTH  
**WELL AND BORING REPORT**  
 Minnesota Statutes Chapter 1031

Entry Date 06/17/1997  
 Update Date 02/02/2016  
 Received Date

<b>Well Name</b> SKYLINE 2	<b>Township</b> 108	<b>Range</b> 27	<b>Dir Section</b> W 23	<b>Subsection</b> DADBCB	<b>Well Depth</b> 501 ft.	<b>Depth Completed</b> 501 ft.	<b>Date Well Completed</b> 08/15/1977
<b>Elevation</b> 983.7	<b>Elev. Method</b> LiDAR 3m DEM (MNDNR)				<b>Drill Method</b> Cable Tool	<b>Drill Fluid</b>	
<b>Address</b> C/W MANKATO MN 56001					<b>Use</b> public supply/community	<b>Status</b> Active	
<b>Stratigraphy Information</b>					<b>Well Hydrofractured?</b> Yes <input type="checkbox"/> No <input type="checkbox"/>	<b>From</b>	<b>To</b>
<b>Geological Material</b>	<b>From</b>	<b>To (ft.)</b>	<b>Color</b>	<b>Hardness</b>	<b>Casing Type</b> Step down	<b>Joint</b> Welded	
DRIFT	0	261	BROWN		<b>Drive Shoe?</b> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	<b>Above/Below</b> 0 ft.	
SHALE, LIME ROCK	261	480	GRAY		<b>Casing Diameter</b>	<b>Weight</b>	
JORDAN SANDSTONE	480	501	WHITE		8 in. To 297 ft. lbs./ft.	12 in. To 263 ft. 49.5 lbs./ft.	
					<b>Open Hole</b> From 263 ft. To 501 ft.		
					<b>Screen?</b> <input type="checkbox"/>	<b>Type</b>	<b>Make</b>
					<b>Static Water Level</b> 220 ft. land surface	<b>Measure</b>	<b>08/15/1977</b>
					<b>Pumping Level (below land surface)</b>		
					<b>Wellhead Completion</b>		
					Pitless adapter manufacturer	Model	
					<input type="checkbox"/> Casing Protection	<input checked="" type="checkbox"/> 12 in. above grade	
					<input type="checkbox"/> At-grade (Environmental Wells and Borings ONLY)		
					<b>Grouting Information</b>	<b>Well Grouted?</b> <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Not Specified	
					<b>Material</b>	<b>Amount</b>	<b>From To</b>
					neat cement	4.96 Cubic yards	0 ft. 297 ft.
					<b>Nearest Known Source of Contamination</b>		
					feet	Direction	Type
					Well disinfected upon completion?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
					<b>Pump</b> <input type="checkbox"/> Not Installed	<b>Date Installed</b>	<b>08/15/1977</b>
					<b>Manufacturer's name</b>	FLOWAY	
					<b>Model Number</b>	<b>HP</b>	<b>Volt</b>
					6JKL	25	220
					<b>Length of drop pipe</b>	<b>ft</b>	<b>Capacity</b>
					275	150	g.p. Typ <b>Submersible</b>
					<b>Abandoned</b>		
					Does property have any not in use and not sealed well(s)? <input type="checkbox"/> Yes <input type="checkbox"/> No		
					<b>Variance</b>		
					Was a variance granted from the MDH for this well? <input type="checkbox"/> Yes <input type="checkbox"/> No		
					<b>Miscellaneous</b>		
					<b>First Bedrock</b>	<b>St.Lawrence Formation</b>	<b>Aquifer</b>
					<b>Last Strat</b>	<b>Wonewoc Sandstone</b>	<b>Depth to Bedrock</b>
							<b>261 ft</b>
					<b>Located by</b> Minnesota Department of Health		
					<b>Locate Method</b> Digitization (Screen) - Map (1:12,000) (>15 meters)		
					<b>System</b>	<b>UTM - NAD83, Zone 15, Meters</b>	<b>X 417525 Y 4888173</b>
					<b>Unique Number Verification</b>	<b>Info/GPS from data</b>	<b>Input Date</b>
							<b>08/31/1993</b>
					<b>Angled Drill Hole</b>		
					<b>Well Contractor</b>		
					<b>Mccarthy Well Co.</b>	<b>27022</b>	<b>MCARTHY, M.</b>
					<b>Licensee Business</b>	<b>Lic. or Reg. No.</b>	<b>Name of Driller</b>
<b>Remarks</b>							
<b>Minnesota Well Index Report</b>					<b>147952</b>		
					Printed on 04/21/2020 HE-01205-15		



**240110**

County Blue Earth  
 Quad Mankato  
 Quad ID 56A

MINNESOTA DEPARTMENT OF HEALTH  
**WELL AND BORING REPORT**  
 Minnesota Statutes Chapter 1031

Entry Date 12/19/2000  
 Update Date 02/02/2016  
 Received Date

<b>Well Name</b> SKYLINE 1	<b>Township</b> 108	<b>Range</b> 27	<b>Dir Section</b> W 23	<b>Subsection</b> DACDBA	<b>Well Depth</b> 440 ft.	<b>Depth Completed</b> 440 ft.	<b>Date Well Completed</b> 00/00/1953
<b>Elevation</b> 988.1	<b>Elev. Method</b> LiDAR 3m DEM (MNDNR)				<b>Drill Method</b> Cable Tool	<b>Drill Fluid</b>	
<b>Address</b>					<b>Use</b> public supply/community	<b>Status</b> Active	
					<b>Well Hydrofractured?</b> Yes <input type="checkbox"/> No <input type="checkbox"/>	<b>From</b>	<b>To</b>
<b>Stratigraphy Information</b>					<b>Casing Type</b> Single casing	<b>Joint</b>	
<b>Geological Material</b> NO RECORDS	<b>From</b> 0	<b>To (ft.)</b> 440	<b>Color</b>	<b>Hardness</b>	<b>Drive Shoe?</b> Yes <input type="checkbox"/> No <input type="checkbox"/>	<b>Above/Below</b>	
					<b>Casing Diameter</b> 8 in. To	<b>Weight</b> 258 ft. lbs./ft.	<b>Hole Diameter</b> in. To ft.
					<b>Open Hole</b> From 258 ft. To 440 ft.		
					<b>Screen?</b> <input type="checkbox"/>	<b>Type</b>	<b>Make</b>
					<b>Static Water Level</b>		
					<b>Pumping Level (below land surface)</b>		
					<b>Wellhead Completion</b>		
					Pitless adapter manufacturer	Model	
					<input type="checkbox"/> Casing Protection	<input type="checkbox"/> 12 in. above grade	
					<input type="checkbox"/> At-grade (Environmental Wells and Borings ONLY)		
					<b>Grouting Information</b>	Well Grouted?	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Not Specified
					<b>Nearest Known Source of Contamination</b>		
					feet	Direction	Type
					Well disinfected upon completion?	<input type="checkbox"/> Yes <input type="checkbox"/> No	
					<b>Pump</b> <input type="checkbox"/> Not Installed	Date Installed	
					Manufacturer's name		
					Model Number	HP	Volt
					Length of drop pipe	ft	Capacity 55 g.p. Typ Submersible
					<b>Abandoned</b>		
					Does property have any not in use and not sealed well(s)? <input type="checkbox"/> Yes <input type="checkbox"/> No		
					<b>Variance</b>		
					Was a variance granted from the MDH for this well? <input type="checkbox"/> Yes <input type="checkbox"/> No		
					<b>Miscellaneous</b>		
					First Bedrock	Aquifer	Tunnel City-
					Last Strat no record	Depth to Bedrock	ft
					Located by Minnesota Department of Health		
					Locate Method Digitization (Screen) - Map (1:12,000) (>15 meters)		
					System UTM - NAD83, Zone 15, Meters	X 417444	Y 4888123
					Unique Number Verification	Info/GPS from data	Input Date 08/31/1993
					<b>Angled Drill Hole</b>		
					<b>Well Contractor</b>		
					Minnesota Department of	MDH	
					Licensee Business	Lic. or Reg. No.	Name of Driller
<b>Remarks</b>							
<b>Minnesota Well Index Report</b>					<b>240110</b>		
					Printed on 04/21/2010 HE-01205-15		

# Appendix E: Tower Inspection

**2018 Inspection Report**  
**Skyline, MN**  
50,000 Gallon Cone top



Prepared by:  
**Chad Edwards**  
Maguire Iron Field Representative  
605-759-4957 cell

Box 1446  
Falls, SD 57101  
Phone (605) 334-9749  
(605) 334-9752



**WATER TOWER SPECIALISTS**  
Established 1915  
New and Used Tanks  
www.maguireiron.com

## Inspection Report

11/30/2018

Customer Acceptance Form

Skyline Minnesota

RE: Water Storage Tank Inspection

Order: 1530264

50,000 gallon cone top

The water storage tank was cleaned and inspected by our crew as per contract. Enclosed please find an inspection report for your file.

We would submit the following recommendations and estimates that may assist you in planning for future tank maintenance:

**Interior Painting:** Visual inspection of interior was difficult due to the tower being full and the heavy staining did not allow for clarity of condition.

**Exterior Painting:** Exterior paint appears to have typical areas of failures. The amount of antennas on this handrail exceeds the load limit for safety by leaps and bounds. This is very unsafe and OSHA would impose fines if they saw this. The cat walk has electronics blocking proper movement around the tower.

**Safety Upgrades:** Ladders are not up to OSHA standards. All ladders need a cable style safety climb for OSHA standards.

Thank you for the opportunity of servicing your tank. Should you require any additional information or documentation, contact our offices.

Sincerely,

Chad Edwards  
605-759-4957

Field Representative

10 N. Minnesota Ave  
Sioux Falls, SD 57104  
Phone (605) 334-9749  
Fax (605) 334-9752



**WATER TOWER SPECIALISTS**  
Established 1915  
New and Used Tanks  
www.maguireiron.com

## Customer Acceptance Form

Foreman: Michael Reynolds Date: 11/30/2018

The improvement work performed by Maguire Iron, Inc. for  
Skyline Minnesota

is hereby approved and accepted as having been performed in compliance  
with the agreement(s) thereto.

Brief description of work performed:

Rov inspection

Did we leave a Pressure Relief Valve?  Yes  No

If yes, Qty: \_\_\_\_\_ x \$ 750.00 = Total: \$ 0.00

*\$750.00 will be billed to the Owner for each Pressure Relief Valves (PRV) that is left behind. After the PRV(s) is returned, we will credit the \$750.00 per PRV back to the Owner. Please mail them back to our physical address at the top of this form to receive your account credit. Mark your package clearly to assure the credit goes to the proper account.*

Official: City clerk

Title: Water superintendent

Phone: 507-345-5390

Signature: City clerk was not available

P.O. Box 1446  
Doux Falls, SD 57101  
Phone (605) 334-9749  
Fax (605) 334-9752



**WATER TOWER SPECIALISTS**  
Established 1915  
New and Used Tanks  
www.maguireiron.com

## Inspection Report

Client: Skyline Minnesota Date: 11/30/2018 Inspection Type: ROV

### GENERAL INFORMATION

Style: Cone Tank Size: 50,000 gallons Low Water Line:          feet  
Location/Access: In town Fence: Yes Power Lines (10ft): No

### FOUNDATION

Vegetation Encroachment: No Foundation Condition: Good Grout Condition: Fair

PIPE VAULT:          Gate Valve Size:          " Diameter

Material: Steel Pipe Size: 8" Dia. Large Dia Riser: N/A Drum Diameter:          " Diameter  
Cat-Walk: No Frost Jacket: ISO (Foam) Top Collar: Yes  
Insulation Joint: Yes Re-Circ System: No Mixer System: No

### INLET FLOW

Material: Steel Size: 4" Dia. Flapper/Screen: Screen Ground Level: Yes  
Outlet Plug: T-Plug Clean-Out Line: No No-Freeze Valve: No

### EXTERIOR

Style: Cone Roof Support: No Attachment: Brackets - Fair Eave Gaps: No  
Condition: Good Spider Rods & Hub: Yes Lap Seams: Good  
Hatch Lock: Locked Penetrations: No --> Describe:           
Safety Rail: No Antennas: Yes --> Describe: On hand rail. Very unsafe load on tower hand rail.

### EXTERIOR

Coating Type: Aluminum Coating Condition: Good Ladder: Yes  
Safety Climb: No Anti-Climb: Leg Plates Lettering/Logo: Block letters  
Remarks: Typical corrosion areas. All the antennas pose an unsafe exposure while on the balcony as well as the amount of weight being added to the handrail.

### INTERIOR - WET

Coating Type: Epoxy Coating Condition: Fair Active Pitting: Yes  
Safety Climb: No Safety Climb: No Riser Safety: None Present  
Remarks: Hard to get a good inspection when the tower is full of water.

### INTERIOR - DRY

Coating Type: N/A Coating Condition: N/A Lighting: N/A  
Safety Climb: N/A Safety Climb: N/A  
Remarks:         

### AWWA INSPECTION

1st Access: Non-Compliant Safety Climb: Non-Compliant Anti-Climb: Compliant  
Hatch: Compliant 2nd Access: Non-Compliant Vent: Non-Compliant  
Overflow: Compliant Rallings: Non-Compliant

INTERNAL CONDITION: Compliant Amount & Type of Sediment: Sand

INTERNAL CORROSION: No Amount of HTH Used:         

INSPECTED BY: Michael Reynolds REVIEWED BY: Chad Edwards DATE: 11/30/2018

Services:  New Tanks and Towers  Fabricating  Erecting  Repairing  Painting  New and Used Tanks

P.O. Box 1446  
 Sioux Falls, SD 57101  
 Phone (605) 334-9749  
 Fax (605) 334-9752



**WATER TOWER SPECIALISTS**  
 Established 1915  
 New and Used Tanks  
 www.maguireiron.com

**OSHA & AWWA Checklist for Safety and Sanitation  
 Potable Water Tanks and Towers**

Owner: Skyline Minnesota Date: 11/30/2018 Leg Height: \_\_\_\_\_  
 Tank Size: 50,000 gallons Tank Style: Cone Tank Height: \_\_\_\_\_

Inspected Item	Standard	Actual	Comment	Need Check
<b>Ladders:</b>				
Rung Size	3/4"	3/4"		
Width	16"	16"		
Step Height	12"	12"		
Side Rails	2" x 3/8"	2" x 3/8"		
Toe Space	7"	5.5"		
Roof Ladder	Secured	Y		
Shell Ladder	Secured	Y		
Leg Ladder	Required	Yes		
Safety Climb	Required	No	Needs cable style safety climb device on all ladders	✓
Anti-Climb Gate	Required	Leg Plates		
<b>Handrailings:</b>				
Height	42"	35"	Not tall enough for OSHA compliance	✓
Mid-Rail	2" x 1/4"	NONE	No midrail on handrail "V" type handrail	✓
Toe Board	4" x 1/4"	2.75"	Not tall enough for OSHA compliance	✓
Pass-Through	Required	Y		
Chains	Required	No	Needs safety chains for climber safety	✓
<b>Openings:</b>				
Roof Man Way	24"	24"		
Second Access	24"	NONE	Needs second egress for OSHA compliance	✓
Curb Height	4"	6"		
Overhang	2"	2"		
Vent	Size	No vent	Final ball, roof vents at the eve to shell connecting	✓
Screen	Frost-Proof	NO	Needs frost free vent.	✓
Riser Man Way	24"	NO		
<b>Overflow:</b>				
Size		4" Dia.		
Screen	Required	Y		
To ground	12" - 24"	12"		

The owners water tank and structure have been inspected and documented for compliance with the current American Water Works Association (AWWA), Occupation Safety & Health Act (OSHA) and the appropriate State Sanitation Code for Potable Water Tanks.

Deficiencies are noted and upon request, recommendations will be made to bring the tank and structure into compliance.

Inspected by: Michael Reynolds

Maguire Iron is not responsible for errors or omissions in the code, and has been diligent in assessing the above structure to the standards applicable at the time of the inspection.

Water Tanks and Towers    Fabricating    Erecting    Repairing    Painting    New and Used Tanks

Notes for Salesman:

---

---

---

---

Notes for Next Clean Out:

---

---

---

---

Foreman: Michael Reynolds      Date: 11/30/2018

a  
W  
e  
ver  
  
ior  
fety



# Appendix F: Cost Estimates

# WATER SYSTEM IMPROVEMENTS

## SKYLINE, MN

### ALTERNATIVE 1 - WATER SUPPLY AND TREATMENT

Location: Skyline, Minnesota

ISG Project #: 20-24060

Date: September 2020

#### ENGINEER'S OPINION OF PROBABLE COST

ITEM NO.	CONSTRUCTION ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL AMOUNT
1	MOBILIZATION (15%)	LS	1	\$ 35,250	\$ 35,250
2	*SITE IMPROVEMENTS	LS	1	\$ 20,000	\$ 20,000
3	WELL PUMP REPLACEMENT	EA	2	\$ 12,000	\$ 24,000
4	WELL #1 REMEDIATION	LS	1	\$ 25,000	\$ 25,000
5	REPLACE PUMP HOUSE PIPING	LS	1	\$ 30,000	\$ 30,000
6	CHEMICAL FEED PUMPS, PIPING, AND SECONDARY CONTAINMENT	LS	1	\$ 36,000	\$ 36,000
7	GENERATOR, SITE ELECTRICAL SERVICES, & CONTROLS	LS	1	\$ 100,000	\$ 100,000
<b>CONSTRUCTION COSTS</b>					<b>\$ 270,250</b>
<b>10% CONTINGENCY</b>					<b>\$ 27,025</b>
<b>ENGINEERING PROFESSIONAL SERVICES</b>					<b>\$ 70,000</b>
<b>TOTAL PROJECT COST</b>					<b>\$ 367,275</b>

\*YARD PIPING, CONNECTIONS, VALVES, HYDRANTS, ROCK, MATERIAL TESTING, TRAFFIC CONTROL

# WATER SYSTEM IMPROVEMENTS

## SKYLINE, MN

### ALTERNATIVE 2 - WATER SUPPLY, TREATMENT, AND TOWER REHABILITATION

Location: Skyline, Minnesota

ISG Project #: 20-24060

Date: September 2020

#### ENGINEER'S OPINION OF PROBABLE COST

ITEM NO.	CONSTRUCTION ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL AMOUNT
1	MOBILIZATION (7.5%)	LS	1	\$ 42,375	\$ 42,375
2	*SITE IMPROVEMENTS	LS	1	\$ 20,000	\$ 20,000
3	WELL PUMP REPLACEMENT	EA	2	\$ 12,000	\$ 24,000
4	WELL #1 REMEDIATION	LS	1	\$ 25,000	\$ 25,000
5	REPLACE PUMP HOUE PIPING	LS	1	\$ 30,000	\$ 30,000
6	CHEMICAL FEED PUMPS, PIPING, AND SECONDARY CONTAINMENT	LS	1	\$ 36,000	\$ 36,000
7	50,000 GALLON WATER TOWER INTERIOR & EXTERIOR COATINGS	LS	1	\$ 225,000	\$ 225,000
8	WATER TOWER SAFETY UPGRADES, TELEMETRY & CONTROLS	LS	1	\$ 70,000	\$ 70,000
9	REPLACE WATER TOWER RISER PIPE	LS	1	\$ 35,000	\$ 35,000
10	GENERATOR, SITE ELECTRICAL SERVICES, & CONTROLS	LS	1	\$ 100,000	\$ 100,000
<b>CONSTRUCTION COSTS</b>					<b>\$ 607,375</b>
<b>10% CONTINGENCY</b>					<b>\$ 60,738</b>
<b>ENGINEERING PROFESSIONAL SERVICES</b>					<b>\$ 100,000</b>
<b>TANK INSPECTION SERVICES</b>					<b>\$ 50,000</b>
<b>TOTAL PROJECT COST</b>					<b>\$ 818,113</b>

\*YARD PIPING, CONNECTIONS, VALVES, HYDRANTS, ROCK, MATERIAL TESTING, TRAFFIC CONTROL

# WATER SYSTEM IMPROVEMENTS

## SKYLINE, MN

### ALTERNATIVE 3 - WATER TOWER REPLACEMENT

Location: Skyline, Minnesota

ISG Project #: 20-24060

Date: September 2020

#### ENGINEER'S OPINION OF PROBABLE COST

ITEM NO.	CONSTRUCTION ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL AMOUNT
1	MOBILIZATION (5%)	LS	1	\$ 38,500	\$ 38,500
2	*SITE IMPROVEMENTS	LS	1	\$ 35,000	\$ 35,000
3	50,000 GALLON WATER TOWER (w/FOUNDATION, PAINT, TANK ELECTRICAL, AND BASED ON THE EAST LOCATION ON-SITE)	LS	1	\$ 560,000	\$ 560,000
4	MIXING AND RECIRCULATION SYSTEM	LS	1	\$ 35,000	\$ 35,000
5	EXISTING WATER TOWER DEMOLITION	LS	1	\$ 40,000	\$ 40,000
6	GENERATOR, SITE ELECTRICAL SERVICES, & CONTROLS	LS	1	\$ 100,000	\$ 100,000
<b>CONSTRUCTION COSTS</b>					<b>\$ 808,500</b>
<b>10% CONTINGENCY</b>					<b>\$ 80,850</b>
<b>ENGINEERING PROFESSIONAL SERVICES</b>					<b>\$ 115,000</b>
<b>TANK INSPECTION SERVICES</b>					<b>\$ 70,000</b>
<b>TOTAL PROJECT COST</b>					<b>\$ 1,074,350</b>

\*YARD PIPING, CONNECTIONS, VALVES, HYDRANTS, ROCK, MATERIAL TESTING, TRAFFIC CONTROL

# WATER SYSTEM IMPROVEMENTS

## SKYLINE, MN

### ALTERNATIVE 4 - WATER SUPPLY, TREATMENT REHABILITATION, AND TOWER REPLACEMENT

Location: Skyline, Minnesota

ISG Project #: 20-24060

Date: September 2020

#### ENGINEER'S OPINION OF PROBABLE COST

ITEM NO.	CONSTRUCTION ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL AMOUNT
1	MOBILIZATION (5%)	LS	1	\$ 44,250	\$ 44,250
2	*SITE IMPROVEMENTS	LS	1	\$ 35,000	\$ 35,000
3	WELL PUMP REPLACEMENT	EA	2	\$ 12,000	\$ 24,000
4	WELL #1 REMEDIATION	LS	1	\$ 25,000	\$ 25,000
5	REPLACE PUMP HOUSE PIPING	LS	1	\$ 30,000	\$ 30,000
6	CHEMICAL FEED PUMPS, PIPING, AND SECONDARY CONTAINMENT	LS	1	\$ 36,000	\$ 36,000
7	50,000 GALLON WATER TOWER (w/FOUNDATION, PAINT, TANK ELECTRICAL, AND BASED ON THE EAST LOCATION ON-SITE)	LS	1	\$ 560,000	\$ 560,000
8	MIXING AND RECIRCULATION SYSTEM	LS	1	\$ 35,000	\$ 35,000
9	EXISTING WATER TOWER DEMOLITION	LS	1	\$ 40,000	\$ 40,000
10	GENERATOR, SITE ELECTRICAL SERVICES, & CONTROLS	LS	1	\$ 100,000	\$ 100,000
<b>CONSTRUCTION COSTS</b>					<b>\$ 929,250</b>
<b>10% CONTINGENCY</b>					<b>\$ 92,925</b>
<b>ENGINEERING PROFESSIONAL SERVICES</b>					<b>\$ 115,000</b>
<b>TANK INSPECTION SERVICES</b>					<b>\$ 70,000</b>
<b>TOTAL PROJECT COST</b>					<b>\$ 1,207,175</b>

\*YARD PIPING, CONNECTIONS, VALVES, HYDRANTS, ROCK, MATERIAL TESTING, TRAFFIC CONTROL